PATENT COOPERATION TREA[illegible] 09/701809

From the INTERNATIONAL SEARCHING AUTHORITY

To:
Murgiana Haq
Farah Namazie
HAQ & NAMAZIE PARTNERSHIP
Robinson Road Post Office,
P.O.Box 765,
Singapore 901515
REPUBLIC OF SINGAPORE

PCT

NOTIFICATION OF TRANSMITTAL OF THE INTERNATIONAL SEARCH REPORT OR THE DECLARATION

(PCT Rule 44.1)

| | |
|---|---|
| Applicant's or agent's file reference SY5000149WOF | Date of mailing *(day/month/year)* 21 Mai. 1999 (21.05.99) |
| | **FOR FURTHER ACTION** See paragraphs 1 and 4 below |
| International application No. PCT / SG 98/00039 | International filing date *(day/month/year)* 1 Jun. 1998 (01.06.98) |
| Applicant HO, ANTHONY TONG SHUEN et al. | |

1. [X] The applicant is hereby notified that the international search report has been established and is transmitted herewith.

**Filing of amendments and statement under Article 19:**
The applicant is entitled, if he so wishes, to amend the claims of the international application (see Rule 46):

**When?** The time limit for filing such amendments is normally two months from the date of transmittal of the international search report; however, for more details, see the notes on the accompanying sheet.

**Where?** Directly to the International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland
Facsimile No.: (41-22) 740.14.35

**For more detailed instructions,** see the notes on the accompanying sheet.

2. [ ] The applicant is hereby notified that no international search report will be established and that the declaration under Article 17(2)(a) to that effect is transmitted herewith.

3. [ ] **With regard to the protest** against payment of (an) additional fee(s) under Rule 40.2, the applicant is notified that:

[ ] the protest together with the decision thereon has been transmitted to the International Bureau together with the applicant's request to forward the texts of both the protest and the decision thereon to the designated Offices.

[ ] no decision has been made yet on the protest; the applicant will be notified as soon as a decision is made.

4. **Further action(s):** The applicant is reminded of the following:

Shortly after **18 months** from the priority date, the international application will be published by the International Bureau. If the applicant wishes to avoid or postpone publication, a notice of withdrawal of the international application, or of the priority claim, must reach the International Bureau as provided in Rules 90*bis*.1 and 90*bis*.3, respectively, before the completion of the technical preparations for international publication.

Within **19 months** from the priority date, a demand for international preliminary examination must be filed if the applicant wishes to postpone the entry into the national phase until 30 months from the priority date (in some Offices even later).

Within **20 months** from the priority date, the applicant must perform the prescribed acts for entry into the national phase before all designated Offices which have not been elected in the demand or in a later election within 19 months from the priority date or could not be elected because they are not bound by Chapter II.

| | |
|---|---|
| Name and mailing address of the ISA/ AT<br>AUSTRIAN PATENT OFFICE<br>Kohlmarkt 8-10<br>A-1014 Vienna | Authorized officer<br>Wolf |
| Facsimile No. +43 / 1 / 534 24 - 535 | Telephone No. +43 / 1 / 534 24 - 436 |

Form PCT/ISA/220 (July 1998)

*(See notes on accompanying sheet)*

PATENT COOPERATION TREATY 09/701809

# PCT

## INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

| Applicant's or agent's file reference | FOR FURTHER ACTION | see Notification of Transmittal of International Search Report (Form PCT/ISA/220) as well as, where applicable, item 5 below. |
|---|---|---|
| SY5000149WOF | | |
| International application No. | International filing date (*day/month/year*) | (Earliest) Priority Date (*day/month/year*) |
| PCT/SG 98/00039 | 01 June 1998 (01.06.98) | 05 January 1998 (05.01.98) |
| Applicant | | |
| HO, ANTHONY TONG SHUEN et al. | | |

This international search report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This international search report consists of a total of 3 sheets.

☐ It is also accompanied by a copy of each prior art document cited in this report.

1. **Basis of the report**
   a. With regard to the **language**, the international search was carried out on the basis of the international application in the language in which it was filed, unless otherwise indicated under this item.
      ☐ the international search was carried out on the basis of a translation of the international application furnished to this Authority (Rule 23.1(b)).
   b. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international search was carried out on the basis of the sequence listing:
      ☐ contained in the international application in written form.
      ☐ filed together with the international application in computer readable form.
      ☐ furnished subsequently to this Authority in written form.
      ☐ furnished subsequently to this Authority in computer readable form.
      ☐ the statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
      ☐ the statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.
2. ☐ **Certain claims were found unsearchable** (See Box I).
3. ☐ **Unity of invention is lacking** (See Box II).
4. With regard to the **title**,
   ☒ the text is approved as submitted by the applicant.
   ☐ the text has been established by this Authority to read as follows:
5. With regard to the **abstract**,
   ☒ the text is approved as submitted by the applicant.
   ☐ the text has been established, according to Rule 38.2(b), by this Authority as it appears in Box III. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.
6. The figure of the **drawings** to be published with the abstract is Figure No.: 7
   ☐ as suggested by the applicant.
   ☒ because the applicant failed to suggest a figure.
   ☐ because this figure better characterizes the invention.
   ☐ None of the figures.

# INTERNATIONAL SEARCH REPORT

International application No.
PCT/SG 98/00039

A. CLASSIFICATION OF SUBJECT MATTER

IPC[6]: G 06 F 12/14

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC[6]: G 06 F 12/14

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

EPODOC, WPI, PAJ

C. DOCUMENTS CONSIDERED TO BE RELEVANT

| Category* | Citation of document, with indication, where appropriate, of the relevant passages | Relevant to claim No. |
|---|---|---|
| A | EP 0 840 513 A (NIPPON ELECTRIC) 06 Msy 1998 (06.05.98), abstract. | 1 |
| T | EP 0 855 681 A (NIPPON TELEGRAPH & TELEPHONE) 29 July 1998 (29.07.98), abstract. | |
| A | EP 0 766 468 A (NIPPON ELECTRIC) 02 April 1997 (02.04.97), abstract. | 1 |

---

☐ Further documents are listed in the continuation of Box C. ☒ See patent family annex.

* Special categories of cited documents:
„A" document defining the general state of the art which is not considered to be of particular relevance
„E" earlier application or patent but published on or after the international filing date
„L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
„O" document referring to an oral disclosure, use, exhibition or other means
„P" document published prior to the international filing date but later than the priority date claimed
„T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
„X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
„Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
„&" document member of the same patent family

| Date of the actual completion of the international search | Date of mailing of the international search report |
|---|---|
| 11 May 1999 (11.05.99) | 21 May 1999 (21.05.99) |

| Name and mailing adress of the ISA/AT | Authorized officer |
|---|---|
| Austrian Patent Office<br>Kohlmarkt 8-10; A-1014 Vienna<br>Facsimile No. 1/53424/535 | Fastenbauer<br>Telephone No. 1/53424/447 |

Form PCT/ISA/210 (second sheet) (July 1998)

INTERNATIONAL SEARCH REPORT
Information on patent family members

International application No.
PCT/SG 98/00039

| In Recherchenbericht angeführtes Patentdokument Patent document cited in search report Document de brevet cité dans le rapport de recherche | Datum der Veröffentlichung Publication date Date de publication | Mitglied(er) der Patentfamilie Patent family member(s) Membre(s) de la famille de brevets | Datum der Veröffentlichung Publication date Date de publication |
|---|---|---|---|
| EP 840513 | | AU A1 44340/97 | 07-05-1998 |
| | | CA AA 2219205 | 05-05-1998 |
| | | EP A2 840513 | 06-05-1998 |
| | | JP A2 10145757 | 29-05-1998 |
| EP 855681 | | EP A2 855681 | 29-07-1998 |
| | | JP A2 10210427 | 07-08-1998 |
| | | JP A2 10257300 | 25-09-1998 |
| | | JP A2 10304323 | 13-11-1998 |
| | | JP A2 11018064 | 22-01-1999 |
| | | JP A2 11041573 | 12-02-1999 |
| EP 766468 | | AU A1 65840/96 | 10-04-1997 |
| | | AU B2 701639 | 04-02-1999 |
| | | CA AA 2184949 | 29-03-1997 |
| | | EP A2 766468 | 02-04-1997 |
| | | JP A2 9191394 | 22-07-1997 |

PATENT COOPERATION TREATY 09/701809 PCT

From the INTERNATIONAL BUREAU

# PCT

## NOTIFICATION OF THE RECORDING OF A CHANGE

(PCT Rule 92bis.1 and Administrative Instructions, Section 422)

To:

HAQ, Murgiana
Haq & Namazie Partnership
Robinson Road
P.O. Box 765
Singapore 901515
SINGAPOUR



| | |
|---|---|
| **Date of mailing** (day/month/year)<br>04 November 1999 (04.11.99) | |
| **Applicant's or agent's file reference**<br>SY5000149WOF | **IMPORTANT NOTIFICATION** |
| **International application No.**<br>PCT/SG98/00039 | **International filing date** (day/month/year)<br>01 June 1998 (01.06.98) |

1. The following indications appeared on record concerning:

[X] the applicant [ ] the inventor [ ] the agent [ ] the common representative

| Name and Address | State of Nationality | State of Residence |
|---|---|---|
| DATAMARK TECHNOLOGIES PTE LTD.<br>Suite 106<br>Innovation Centre, Block 1<br>16 Nanyang Dive<br>Singapore 637722<br>Singapore | SG | SG |
| | Telephone No. | |
| | Facsimile No. | |
| | Teleprinter No. | |

2. The International Bureau hereby notifies the applicant that the following change has been recorded concerning:

[ ] the person [ ] the name [ ] the address [ ] the nationality [ ] the residence

| Name and Address | State of Nationality | State of Residence |
|---|---|---|
| DATAMARK TECHNOLOGIES PTE LTD.<br>Suite 106<br>Innovation Centre, Block 1<br>16 Nanyang Dive<br>Singapore 637722<br>Singapore | SG | SG |
| | Telephone No. | |
| | Facsimile No. | |
| | Teleprinter No. | |

3. Further observations, if necessary:
**Please be advised that Datamark Technologies Pte Ltd. si the applicant for all designated states except the US and messieurs HO and Tam are applicant/inventors for the US only.**

4. A copy of this notification has been sent to:

[X] the receiving Office
[ ] the International Searching Authority
[ ] the International Preliminary Examining Authority
[ ] the designated Offices concerned
[ ] the elected Offices concerned
[ ] other:

| | |
|---|---|
| **The International Bureau of WIPO**<br>**34, chemin des Colombettes**<br>**1211 Geneva 20, Switzerland** | Authorized officer<br>P. Regis |
| Facsimile No.: (41-22) 740.14.35 | Telephone No.: (41-22) 338.83.38 |

Form PCT/IB/306 (March 1994)

002938025

# PATENT COOPERATION TREATY

SY

From the INTERNATIONAL BUREAU

## PCT

### NOTIFICATION OF THE RECORDING OF A CHANGE

(PCT Rule 92bis.1 and Administrative Instructions, Section 422)

To:

HAQ, Murgiana
Haq & Namazie Partnership
Robinson Road
P.O. Box 765
Singapore 901515
SINGAPOUR

| | |
|---|---|
| **Date of mailing** (day/month/year)<br>22 October 1998 (22.10.98) | |
| **Applicant's or agent's file reference**<br>SY5000149WOF | **IMPORTANT NOTIFICATION** |
| **International application No.**<br>PCT/SG98/00039 | **International filing date** (day/month/year)<br>01 June 1998 (01.06.98) |

1. The following indications appeared on record concerning:

[X] the applicant [X] the inventor [ ] the agent [ ] the common representative

| Name and Address | State of Nationality | State of Residence |
|---|---|---|
| HO, Anthony, Tong, Shuen | GB | SG |
| | Telephone No. | |
| | Facsimile No. | |
| | Teleprinter No. | |

2. The International Bureau hereby notifies the applicant that the following change has been recorded concerning:

[ ] the person [X] the name [ ] the address [ ] the nationality [ ] the residence

| Name and Address | State of Nationality | State of Residence |
|---|---|---|
| HO, Anthony, Tung, Shuen | GB | SG |
| | Telephone No. | |
| | Facsimile No. | |
| | Teleprinter No. | |

3. Further observations, if necessary:

4. A copy of this notification has been sent to:

[X] the receiving Office
[X] the International Searching Authority
[ ] the International Preliminary Examining Authority
[ ] the designated Offices concerned
[ ] the elected Offices concerned
[ ] other:

| | |
|---|---|
| **The International Bureau of WIPO**<br>**34, chemin des Colombettes**<br>**1211 Geneva 20, Switzerland**<br>Facsimile No.: (41-22) 740.14.35 | Authorized officer<br>N. Fischer<br>Telephone No.: (41-22) 338.83.38 |

002299393

Form PCT/IB/306 (March 1994)

# PCT

## REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No.

International filing Date

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference *(if desired) (12 characters maximum)* SY5000149WOF

**Box No. I TITLE OF INVENTION**

METHODS FOR EMBEDDING IMAGE, AUDIO AND VIDEO WATERMARKS IN DIGITAL DATA

**Box No. II APPLICANT**

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)*

HO, ANTHONY TONG SHUEN
c/o Nanyang Technological University
School of Electrical & Electronic Engineering
Block S2, Nanyang Avenue
Singapore 639798
Republic of Singapore

[X] This person is also inventor.

Telephone No.

Facsimile No.

Teleprinter No.

State *(i.e. country)* of nationality: GB, CA

State *(i.e. country)* of residence: SG

This person is applicant for the purposes of: [X] all designated States [ ] all designated States except the United States of America [ ] the United States of America only [ ] the States indicated in the Supplemental Box

**Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)**

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)*

TAM SIU CHUNG
c/o Nanyang Technological University
School of Electrical & Electronic Engineering
Block S2, Nanyang Avenue
Singapore 639798
Republic of Singapore

This person is:

[ ] applicant only

[X] applicant and inventor

[ ] inventor only *(If this check-box is marked, do not fill in below.)*

State *(i.e. country)* of nationality: SG

State *(i.e. country)* of residence: SG

This person is applicant for the purposes of: [X] all designated States [ ] all designated States except the United States of America [ ] the United States of America only [ ] the States indicated in the Supplemental Box

[ ] Further applicants and/or (further) inventors are indicated on a continuation sheet.

**Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE**

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: [X] Agent [ ] common representative

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

Murgiana Haq
Farah Namazie
of HAQ & NAMAZIE PARTNERSHIP
Robinson Road, P.O. Box 765,
Singapore 901515

Telephone No. (65) 438 6613

Facsimile No. (65) 438 7383 , (65) 438 7393

Teleprinter No.

[ ] Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondences should be sent.

Box No. V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) *(mark the applicable check-boxes; at least one must be marked)*:

Regional Patent

- ☐ AP **ARIPO Patent:** GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SZ Swaziland, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☐ EA **Eurasian Patent:** AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ EP **European Patent:** AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☐ OA **OAPI Patent:** BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT *(if other kind of protection or treatment desired, specify on dotted line)* .....

National Patent *(if other kind of protection or treatment desired, specify on dotted line)*:

- ☐ AL Albania .....
- ☐ AM Armenia .....
- ☐ AT Austria .....
- ☒ AU Australia .....
- ☐ AZ Azerbaijan
- ☐ BA Bosnia and Herzegovina .....
- ☐ BB Barbados
- ☐ BG Bulgaria .....
- ☐ BR Brazil .....
- ☐ BY Belarus
- ☒ CA Canada
- ☐ CH and LI Switzerland and Liechtenstein
- ☐ CN China .....
- ☐ CU Cuba .....
- ☐ CZ Czech Republic .....
- ☐ DE Germany .....
- ☐ DK Denmark .....
- ☐ EE Estonia .....
- ☐ ES Spain .....
- ☐ FI Finland .....
- ☐ GB United Kingdom
- ☐ GE Georgia .....
- ☐ GH Ghana .....
- ☐ GM Gambia
- ☐ GW Guinea-Bissau .....
- ☐ HU Hungary .....
- ☐ ID Indonesia
- ☐ IL Israel .....
- ☐ IS Iceland
- ☒ JP Japan .....
- ☐ KE Kenya .....
- ☐ KG Kyrgyzstan .....
- ☐ KP Democratic People's Republic of Korea .....
- ☐ KR Republic of Korea .....
- ☐ KZ Kazakhstan .....
- ☐ LC Saint Lucia
- ☐ LK Sri Lanka
- ☐ LR Liberia
- ☐ LS Lesotho .....
- ☐ LT Lithuania
- ☐ LU Luxembourg
- ☐ LV Latvia
- ☐ MD Republic of Moldova .....
- ☐ MG Madagascar .....
- ☐ MK The former Yugoslav Republic of Macedonia .....
- ☐ MN Mongolia
- ☐ MW Malawi .....
- ☐ MX Mexico .....
- ☐ NO Norway
- ☐ NZ New Zealand .....
- ☐ PL Poland .....
- ☐ PT Portugal .....
- ☐ RO Romania
- ☐ RU Russian Federation .....
- ☐ SD Sudan
- ☐ SE Sweden
- ☒ SG Singapore
- ☐ SI Slovenia .....
- ☐ SK Slovakia .....
- ☐ SL Sierra Leone
- ☐ TJ Tajikistan .....
- ☐ TM Turkmenistan .....
- ☐ TR Turkey .....
- ☐ TT Trinidad and Tobago .....
- ☐ UA Ukraine .....
- ☐ UG Uganda .....
- ☒ US United States of America .....
- ☐ UZ Uzbekistan .....
- ☐ VN Viet Nam .....
- ☐ YU Yugoslavia .....
- ☐ ZW Zimbabwe .....

Check-boxes reserved for designating States (for the purposes of a national patent) which have become party to the PCT after issuance of this sheet:

- ☐ .....
- ☐ .....
- ☐ .....

**In addition to the designations made above,** the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except the designation(s) of _____.

The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. *(Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)*

**Box No. VI PRIORITY CLAIM** Further priority claims are indicated in the Supplemental Box ☐

The priority of the following earlier application(s) is hereby claimed:

| Country *(in which, or for which, the application was filed)* | Filing Date *(day/month/year)* | Application No. | Office of filing *(only for regional or international application)* |
|---|---|---|---|
| Item (1) | | | |
| Item (2) | | | |
| Item (3) | | | |

Mark the following check-box if the certified copy of the earlier application is to be issued by the Office which for the purposes of the present international application is the receiving Office *(a fee may be required)*:

☐ The receiving Office is hereby requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) identified above as item(s) : _____

**Box No. VII INTERNATIONAL SEARCHING AUTHORITY**

**Choice of International Searching Authority (ISA)** *(If two or more International Searching authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):* ISA / AT

**Earlier search** Fill in where a search (international, international-type or other) by the International Searching Authority has already been carried out or requested and the Authority is now requested to base the international search, to the extent possible, on the results of that earlier search. Identify such search or request either by reference to the relevant application (or the translation thereof) or by reference to the search request:

Country (or regional Office): Date (day/month/year): Number:

**Box No. VIII CHECK LIST**

This international application contains the following number of sheets:

| | | |
|---|---|---|
| 1. request | 3 | sheets |
| 2. description | 15 | sheets |
| 3. claims | 8 | sheets |
| 4. abstract | 1 | sheets |
| 5. drawings | 10 | sheets |
| **Total** | 37 | sheets |

This international application is accompanied by the item(s) marked below:

1. [X] separate signed power of attorney
2. [X] copy of general power of attorney
3. [ ] statement explaining lack of signature
4. [ ] priority document(s) *identified in Box No. VI as item(s):*
5. [X] fee calculation sheet
6. [ ] separate indications concerning deposited microorganisms
7. [ ] nucleotide and/or amino acid sequence listing (diskette)
8. [ ] other *(specify):*

Figure No. _____ of the drawings (if any) should accompany the abstract when it is published.

**Box No. IX SIGNATURE OF APPLICANT OR AGENT**

*Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).*

Farah Namazie
Agent

For receiving Office use only

1. Date of actual receipt of the purported international application:
2. Drawings:
   - ☐ received:
   - ☐ not received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purpose international application:
4. Date of timely receipt of the required Corrections under PCT Article 11(2):
5. International Searching Authority Specified by the applicant: ISA /
6. ☐ Transmittal of search copy delayed until search fee is paid

For International Bureau use only

Date of receipt of the record copy By the International Bureau:

*This sheet is not part of and does not count as a sheet of the international application.*

# PCT

## FEE CALCULATION SHEET
**Annex to the Request**

For receiving Office use only

International application No.

Date stamp of the receiving Office

Applicant's or agent's file reference: SY5000149WOF

Applicant: Ho, Anthony Tung Shuen
Tam Siu Chung

### CALCULATION OF PRESCRIBED FEES

1. TRANSMITTAL FEE ..... 135 T

2. SEARCH FEE ..... 287 S

International search to be carried out by: AT

*(If two or more International Searching Authorities are competent in relation to the international application, indicate the name of the Authority which is chosen to carry out the international search.)*

3. INTERNATIONAL FEE

**Basic Fee**

The international application contains 37 sheets.

first 30 sheets ..... 690 $b_1$

7 (remaining sheets) x 16 (additional amount) = 112 $b_2$

Add amounts entered at $b_1$ and $b_2$ and enter total at B ..... 802 B

**Designation Fees**

The international application contains 6 designations.

6 (number of designation fees payable *(maximum 11)*) x 160 (amount of designation fee) = 960 D

Add amounts entered at B and D and enter total at I ..... 1762 I

*(Applicants from certain States are entitled to a reduction of 75% of the international fee. Where the applicant is (or all applicants are) so entitled, the total to be entered at I is 25% of the sum of the amounts entered at B and D.)*

4. FEE FOR PRIORITY DOCUMENT ..... 0 P

5. TOTAL FEES PAYABLE
Add amounts entered at T, S, I and P, and enter total in the TOTAL box.. 2184 TOTAL

☐ The designation fees are not paid at this time.

**Mode of Payment**

☐ authorization to charge deposit account *(see below)*
☐ bank draft
☐ coupons
☒ cheque
☐ cash
☐ other *(specify)*:
☐ postal money order
☐ revenue stamps

**Deposit Account Authorization** *(this mode of payment may not be available at all receiving Offices)*

The RO/ _____

☐ is hereby authorized to charge the total fees indicated above to my deposit account.

☐ is hereby authorized to charge any deficiency or credit any overpayment in the total fees indicated above to my deposit account.

☐ is hereby authorized to charge the fee for preparation and transmittal of the priority document to the International Bureau of WIPO to my deposit account.

Deposit Account Number _____ Date *(day/month/year)* _____ Signature _____



*See Notes to the fee calculation sheet*

*The demand must be filed directly with the competent International Preliminary Examining Authority or, if two or more Authorities are competent, with the one chosen by the applicant. The full name or two-letter code of that Authority may be indicated by the applicant on the line below :*

IPEA / AU

99/701809

**CHAPTER II**

# PCT
## DEMAND

under Article 31 of the Patent Cooperation Treaty:
The undersigned requests that the international application specified below be the subject of International preliminary examination according to the Patent Corporation Treaty and hereby elects all eligible States (except where otherwsie indicated).

For International Preliminary Examining Authority use only

| Identification of IPEA | Date of receipt of DEMAND |
|---|---|
| | |

**Box No. I IDENTIFICATION OF THE INTERNATIONAL APPLICATION**

Applicant's or agent's file reference: **SY5000149WOF**

| International application No. | International filing date *(day/month/year)* | (Earliest) Priority date *(day/month/year)* |
|---|---|---|
| **PCT/SG98/00039** | **01 June 1998 (01.06.98)** | |

Title of invention
**METHODS FOR EMBEDDING IMAGE, AUDIO AND VIDEO WATERMARKS IN DIGITAL DATA**

**Box No. II APPLICANT(S)**

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country)*

**DATAMARK TECHNOLOGIES PTE LTD**

**SUITE 106, INNOVATION CENTRE, BLOCK 1**
**16 NANYANG DRIVE**
**SINGAPORE 637722**
**REPUBLIC OF SINGAPORE**

Telephone No.:

Facsimile No.:

Teleprinter No.:

| State *(i.e. country)* of nationality: | State *(i.e. country)* of residence: |
|---|---|
| **SG** | **SG** |

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

**HO, ANTHONY TUNG SHUEN**
**C/O NANYANG TECHNOLOGICAL UNIVERSITY,**
**SCHOOL OF ELECTRICAL & ELECTRONIC ENGINEERING**
**BLOCK S2, NANYANG AVENUE, SINGAPORE 639798**
**REPUBLIC OF SINGAPORE**

| State *(i.e. country)* of nationality: | State *(i.e. country)* of residence: |
|---|---|
| **CA** | **SG** |

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

**TAM SIU CHUNG**
**C/O NANYANG TECHNOLOGICAL UNIVERSITY,**
**SCHOOL OF ELECTRICAL & ELECTRONIC ENGINEERING**
**BLOCK S2, NANYANG AVENUE, SINGAPORE 639798**
**REPUBLIC OF SINGAPORE**

| State *(i.e. country)* of nationality: | State *(i.e. country)* of residence: |
|---|---|
| **SG** | **SG** |

☐ Further applicants are indicated on a continuation sheet.

International application No.
PCT/SG98/00039

**Box No. III AGENT OF COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE**

The following person is [X] agent [ ] common representative

and [X] has been appointed earlier and represents the applicant(s) also for international preliminary examination.

[ ] is been appointed and any earlier appointment of (an) agent(s) / common representative is hereby revoked.

[ ] is hereby appointed, specifically for the procedure before the International Preliminary Examining Authority, in addition to the agent(s) / common representative appointed earlier.

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country)*

**NAMAZIE, FARAH**
**HAQ, MURGIANA**
**OF HAQ & NAMAZIE PARTNERSHIP**
**ROBINSON ROAD POST OFFICE,**
**P.O. BOX 765, SINGAPORE 901515**
**REPUBLIC OF SINGAPORE**

Telephone No.: **65 438 6613**

Facsimile No.: **65 438 7383**

Teleprinter No.:

[ ] **Address for correspondence:** Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

**Box No. IV BASIS FOR INTERNATIONAL PRELIMINARY EXAMINATION**

**Statement concerning amendments:***

1. The applicant wishes the International Preliminary Examining Authority **to start on the basis of:**

   [X] the international application as originally filed

   the description [X] as originally filed
   [ ] as amended under Article 34

   the claims [X] as originally filed
   [ ] as amended under Article 19 (together with any accompanying statement)
   [ ] as amended under Article 34

   the drawings [X] as originally filed
   [ ] as amended under Article 34

2. [ ] The applicant wishes any amendment to the claims under Article 19 to be considered as reversed.

3. [ ] The applicant wishes the start of the international preliminary examination **to be postponed** until the expiration of 20 months from the priority date unless the International Preliminary Examining Authority receive a copy of any amendments made under Article 19 or a notice from the applicant that he does not wish to make such amendments (Rule 69.1(d)). *This check-box may be marked only where the time limit under Article 19 has not yet expired.)*

* Where no check-box is marked, international preliminary examination will start on the basis of the international application as originally filed or, where a copy of amendments to the claims under Article 19 and/or amendments of the international application under Article 34 are received by the International Preliminary Examining Authority before it has begun to draw up a written opinion or the international preliminary examination report, as so amended.

**Language for the purposes of international preliminary examination: ENGLISH**

[X] which is the language in which the international application was filed.

[ ] which is the language of a translation furnished for the purposes of international search.

[ ] which is the language of publication of the international application.

[ ] which is the language of the translation (to be) furnished for the purposes of international preliminary examination.

**Box No. V ELECTION OF STATES**

The applicant hereby **elects all eligible states** *(that is, all States which have been designated and which are bound by Chapter II of the PCT)*

excluding the following States which the applicant wishes **not to elect:**

International application No.
**PCT/SG98/00039**

**Box No. VI CHECK LIST**

The demand is accompanied by the following elements, in the language referred to in Box No. IV, for the purposes of international preliminary examination:

| | | | | | For International Preliminary Examining Authority use only | |
|---|---|---|---|---|---|---|
| | | | | | received | not received |
| 1. | translation of international application | : | - | sheets | ☐ | ☐ |
| 2. | amendments under Article 34 | : | - | sheets | ☐ | ☐ |
| 3. | copy (or, where required, translation) of amendments under Article 19 | : | - | sheets | ☐ | ☐ |
| 4. | copy (or, where required, translation) of statement under Article 19 | : | - | sheets | ☐ | ☐ |
| 5. | letter | : | 1 | sheets | ☐ | ☐ |
| 6. | other *(specify)* | : | - | sheets | ☐ | ☐ |

The demand is also accompanied by the item(s) marked below :

1. [X] fee calculation sheet
2. [ ] separate signed power of attorney
3. [X] copy of general power of attorney; reference number, if any
4. [ ] statement explaining lack of signature
5. [ ] nucleotide and or amino acids listing in computer readable form
6. [X] other *(specify)*: **Form PCT/IB/306 dated 04 November 1999**

**Box No. VII SIGNATURE OF APPICANT, AGENT OR COMMON REPRESENTATIVE**

*Next to each signature, indicate the name of the person signing and capacity in which the person signs (if such capacity is not obvious from reading the demand).*

**Namazie, Farah**
**Agent**

For International Preliminary Examining Authority use only

1. Date of actual receipt of DEMAND:
2. Adjusted date of receipt of demand due to CORRECTIONS under Rule 60.1(b):
3. [ ] The date of receipt of the demand is AFTER the expiration of 19 months from the priority date and item 4 or 5, below, does not apply. [ ] The applicant has been informed accordingly.
4. [ ] The date of receipt of the demand is WITHIN the period of 19 months from the priority date as extended by virtue of Rule 80.5.
5. [ ] Although the date of receipt of the demand is after the expiration of 19 months from the priority date, the delay in arrival is EXCUSED pursuant to Rule 82.

For International Bureau use only

Demand received from IPEA on:



*See Notes to the demand form*

# PCT

**CHAPTER II**

## FEE CALCULATION SHEET

**Annex to the Demand for international preliminary examination**

| | |
|---|---|
| International application No. | PCT/SG98/00039 |
| Applicant's or agent's file reference | SY5000149WOF |

For International Preliminary Examination Authority use only

Date stamp of the IPEA

Applicant

**DATAMARK TECHNOLOGIES PTE LTD, et al.**

**Calculation of prescribed fees**

| | | | |
|---|---|---|---|
| 1. | Preliminary examination fee | AUD 450 | P |
| 2. | Handling fee *(Applicants from certain States are entitled to a reduction of 75% of the handling fee. Where the applicant is (for all applicants are) so entitled, the amount to be entered at H is 25% of the handling fee.* | AUD 224 | H |
| 3. | Total of prescribed fees Add the amounts entered at P and H and enter total in the TOTAL box | AUD 674 | TOTAL |

**Mode of Payment**

| | | | |
|---|---|---|---|
| ☐ | authorization to charge deposit account with the IPEA (see below) | ☐ | cash |
| ☐ | cheque | ☐ | revenue stamps |
| ☐ | postal money order | ☐ | coupons |
| ☒ | bank draft | ☐ | others *(specify)*: |

**Deposit Account Authorization** *(this mode of payment may not be available at all IPEAs)*

The IPEA/ _____

☐ is hereby authorized to charge the total fees indicated above to my deposit account.

☐ *(this check-box may be marked only if the conditions for deposit accounts of the IPEA so permit)* is hereby authorized to charge any deficiency or credit any overpayment in the total fees indicated above to my deposit account.

Deposit Account Number | Date *(day/month/year)* | Signature

# PATENT COOPERATION TREATY

From the INTERNATIONAL BUREAU

## PCT

### NOTIFICATION OF ELECTION

(PCT Rule 61.2)

To:

Assistant Commissioner for Patents
United States Patent and Trademark Office
Box PCT
Washington, D.C.20231
ÉTATS-UNIS D'AMÉRIQUE

in its capacity as elected Office

| | |
|---|---|
| **Date of mailing** (day/month/year)<br>21 February 2000 (21.02.00) | |
| **International application No.**<br>PCT/SG98/00039 | **Applicant's or agent's file reference**<br>SY5000149WOF |
| **International filing date** (day/month/year)<br>01 June 1998 (01.06.98) | **Priority date** (day/month/year) |
| **Applicant**<br>HO, Anthony, Tung, Shuen et al | |

1. The designated Office is hereby notified of its election made:

   [X] in the demand filed with the International Preliminary Examining Authority on:

   24 December 1999 (24.12.99)

   [ ] in a notice effecting later election filed with the International Bureau on:

2. The election [X] was

   [ ] was not

   made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

| | |
|---|---|
| **The International Bureau of WIPO**<br>**34, chemin des Colombettes**<br>**1211 Geneva 20, Switzerland** | Authorized officer<br>Olivia RANAIVOJAONA |
| Facsimile No.: (41-22) 740.14.35 | Telephone No.: (41-22) 338.83.38 |

Form PCT/IB/331 (July 1992)

3119944

PATENT COOPERATION TREATY

# PCT

## INTERNATIONAL PRELIMINARY EXAMINATION REPORT



(PCT Article 36 and Rule 70)

| | | |
|---|---|---|
| Applicant's or agent's file reference SY5000149WOF | **FOR FURTHER ACTION** | See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416). |
| International application No. PCT/SG 98/00039 | International filing date *(day/month/year)* 1 June 1998 | Priority Date *(day/month/year)* 1 June 1998 |

International Patent Classification (IPC) or national classification and IPC

**Int. Cl.**[7] G06F 12/14

Applicant

DATAMARK TECHNOLOGIES PTE LTD et al

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.

2. This REPORT consists of a total of 3 sheets, including this cover sheet.

☐ This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

These annexes consist of a total of sheet(s).

3. This report contains indications relating to the following items:

| | | |
|---|---|---|
| I | ☒ | Basis of the report |
| II | ☐ | Priority |
| III | ☐ | Non-establishment of opinion with regard to novelty, inventive step and industrial applicability |
| IV | ☐ | Lack of unity of invention |
| V | ☒ | Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement |
| VI | ☐ | Certain documents cited |
| VII | ☐ | Certain defects in the international application |
| VIII | ☐ | Certain observations on the international application |

| | |
|---|---|
| Date of submission of the demand 24 December 1999 | Date of completion of the report 21 February 2000 |
| Name and mailing address of the IPEA/AU<br>AUSTRALIAN PATENT OFFICE<br>PO BOX 200, WODEN ACT 2606, AUSTRALIA<br>E-mail address: pct@ipaustralia.gov.au<br>Facsimile No. (02) 6285 3929 | Authorized Officer<br>**J.W. THOMSON**<br>Telephone No. (02) 6283 2214 |

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.
PCT/SG 98/00039

**I. Basis of the report**

1. With regard to the **elements** of the international application:*

- [X] the international application as originally filed.
- [ ] the description, pages , as originally filed,
  pages , filed with the demand,
  pages , filed with the letter of .
- [ ] the claims, pages , as originally filed,
  pages , as amended (together with any statement) under Article 19,
  pages , filed with the demand,
  pages , filed with the letter of .
- [ ] the drawings, pages , as originally filed,
  pages , filed with the demand,
  pages , filed with the letter of .
- [ ] the sequence listing part of the description:
  pages , as originally filed
  pages , filed with the demand
  pages , filed with the letter of .

2. With regard to the **language**, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.
These elements were available or furnished to this Authority in the following language which is:

- [ ] the language of a translation furnished for the purposes of international search (under Rule 23.1(b)).
- [ ] the language of publication of the international application (under Rule 48.3(b)).
- [ ] the language of the translation furnished for the purposes of international preliminary examination (under Rules 55.2 and/or 55.3).

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, was on the basis of the sequence listing:

- [ ] contained in the international application in written form.
- [ ] filed together with the international application in computer readable form.
- [ ] furnished subsequently to this Authority in written form.
- [ ] furnished subsequently to this Authority in computer readable form.
- [ ] The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
- [ ] The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished

4. [ ] The amendments have resulted in the cancellation of:
   - [ ] the description, pages
   - [ ] the claims, Nos.
   - [ ] the drawings, sheets/fig.

5. [ ] This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2(c)).**

* *Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to this report since they do not contain amendments (Rules 70.16 and 70.17).*

** *Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report*

**V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement**

1. Statement

| | | |
|---|---|---|
| Novelty (N) | Claims 1 - 64 | YES |
| | Claims | NO |
| Inventive step (IS) | Claims 1 - 64 | YES |
| | Claims | NO |
| Industrial applicability (IA) | Claims 1 - 64 | YES |
| | Claims | NO |

2. Citations and explanations (Rule 70.7)

EP 840513 A (NIPPON ELECTRIC) 6 May 1998
EP 855681 A (NIPPON TELEGRAPH & TELEPHONE) 29 July 1998
EP 766468 A (NIPPON ELECTRIC) 2 April 1997

None of these citations discloses the invention as defined in claims 1 to 64.

PATENT COOPERATION TREATY 09/701809

# PCT

## INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

| | | |
|---|---|---|
| Applicant's or agent's file reference SY5000149WOF | **FOR FURTHER ACTION** | See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416). |
| International application No. **PCT/SG 98/00039** | International filing date *(day/month/year)* 1 June 1998 | Priority Date *(day/month/year)* 1 June 1998 |
| International Patent Classification (IPC) or national classification and IPC **Int. Cl.**[7] G06F 12/14 | | |
| Applicant DATAMARK TECHNOLOGIES PTE LTD et al | | |

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.

2. This REPORT consists of a total of 3 sheets, including this cover sheet.

☐ This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

These annexes consist of a total of sheet(s).

3. This report contains indications relating to the following items:

| | | |
|---|---|---|
| I | ☒ | Basis of the report |
| II | ☐ | Priority |
| III | ☐ | Non-establishment of opinion with regard to novelty, inventive step and industrial applicability |
| IV | ☐ | Lack of unity of invention |
| V | ☒ | Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement |
| VI | ☐ | Certain documents cited |
| VII | ☐ | Certain defects in the international application |
| VIII | ☐ | Certain observations on the international application |

| | |
|---|---|
| Date of submission of the demand 24 December 1999 | Date of completion of the report 21 February 2000 |
| Name and mailing address of the IPEA/AU<br>AUSTRALIAN PATENT OFFICE<br>PO BOX 200, WODEN ACT 2606, AUSTRALIA<br>E-mail address: pct@ipaustralia.gov.au<br>Facsimile No. (02) 6285 3929 | Authorized Officer<br>J.W. THOMSON<br>Telephone No. (02) 6283 2214 |

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.
PCT/SG 98/00039

## I. Basis of the report

1. With regard to the **elements** of the international application:*

[X] the international application as originally filed.

[ ] the description, pages , as originally filed,
pages , filed with the demand,
pages , filed with the letter of .

[ ] the claims, pages , as originally filed,
pages , as amended (together with any statement) under Article 19,
pages , filed with the demand,
pages , filed with the letter of .

[ ] the drawings, pages , as originally filed,
pages , filed with the demand,
pages , filed with the letter of .

[ ] the sequence listing part of the description:
pages , as originally filed
pages , filed with the demand
pages , filed with the letter of .

2. With regard to the **language**, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.
These elements were available or furnished to this Authority in the following language which is:

[ ] the language of a translation furnished for the purposes of international search (under Rule 23.1(b)).

[ ] the language of publication of the international application (under Rule 48.3(b)).

[ ] the language of the translation furnished for the purposes of international preliminary examination (under Rules 55.2 and/or 55.3).

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, was on the basis of the sequence listing:

[ ] contained in the international application in written form.

[ ] filed together with the international application in computer readable form.

[ ] furnished subsequently to this Authority in written form.

[ ] furnished subsequently to this Authority in computer readable form.

[ ] The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

[ ] The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished

4. [ ] The amendments have resulted in the cancellation of:

[ ] the description, pages

[ ] the claims, Nos.

[ ] the drawings, sheets/fig.

5. [ ] This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the Supplemental Box (Rule 70.2(c)).**

* *Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to this report since they do not contain amendments (Rules 70.16 and 70.17).*

** *Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report*

**V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement**

1. Statement

| | | | |
|---|---|---|---|
| Novelty (N) | Claims | 1 - 64 | YES |
| | Claims | | NO |
| Inventive step (IS) | Claims | 1 - 64 | YES |
| | Claims | | NO |
| Industrial applicability (IA) | Claims | 1 - 64 | YES |
| | Claims | | NO |

2. Citations and explanations (Rule 70.7)

EP 840513 A (NIPPON ELECTRIC) 6 May 1998
EP 855681 A (NIPPON TELEGRAPH & TELEPHONE) 29 July 1998
EP 766468 A (NIPPON ELECTRIC) 2 April 1997

None of these citations discloses the invention as defined in claims 1 to 64.

09/701809

# INTERNATIONAL SEARCH REPORT

International application No.
PCT/SG 98/00039

A. CLASSIFICATION OF SUBJECT MATTER

IPC[6]: G 06 F 12/14

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC[6]: G 06 F 12/14

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

EPODOC, WPI, PAJ

C. DOCUMENTS CONSIDERED TO BE RELEVANT

| Category* | Citation of document, with indication, where appropriate, of the relevant passages | Relevant to claim No. |
|---|---|---|
| A | EP 0 840 513 A (NIPPON ELECTRIC) 06 Msy 1998 (06.05.98), abstract. | 1 |
| T | EP 0 855 681 A (NIPPON TELEGRAPH & TELEPHONE) 29 July 1998 (29.07.98), abstract. | |
| A | EP 0 766 468 A (NIPPON ELECTRIC) 02 April 1997 (02.04.97), abstract. | 1 |

☐ Further documents are listed in the continuation of Box C. ☒ See patent family annex.

* Special categories of cited documents:
„A" document defining the general state of the art which is not considered to be of particular relevance
„E" earlier application or patent but published on or after the international filing date
„L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
„O" document referring to an oral disclosure, use, exhibition or other means
„P" document published prior to the international filing date but later than the priority date claimed
„T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
„X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
„Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
„&" document member of the same patent family

| Date of the actual completion of the international search | Date of mailing of the international search report |
|---|---|
| 11 May 1999 (11.05.99) | 21 May 1999 (21.05.99) |
| Name and mailing adress of the ISA/AT<br>Austrian Patent Office<br>Kohlmarkt 8-10; A-1014 Vienna<br>Facsimile No. 1/53424/535 | Authorized officer<br>Fastenbauer<br>Telephone No. 1/53424/447 |

Form PCT/ISA/210 (second sheet) (July 1998)

# INTERNATIONAL SEARCH REPORT

Information on patent family members

International application No.
PCT/SG 98/00039

| In Recherchenbericht angeführtes Patentdokument Patent document cited in search report Document de brevet cité dans le rapport de recherche | Datum der Veröffentlichung Publication date Date de publication | Mitglied(er) der Patentfamilie Patent family member(s) Membre(s) de la famille de brevets | Datum der Veröffentlichung Publication date Date de publication |
|---|---|---|---|
| EP 840513 | | AU A1 44340/97 | 07-05-1998 |
| | | CA AA 2219205 | 05-05-1998 |
| | | EP A2 840513 | 06-05-1998 |
| | | JP A2 10145757 | 29-05-1998 |
| EP 855681 | | EP A2 855681 | 29-07-1998 |
| | | JP A2 10210427 | 07-08-1998 |
| | | JP A2 10257300 | 25-09-1998 |
| | | JP A2 10304323 | 13-11-1998 |
| | | JP A2 11018064 | 22-01-1999 |
| | | JP A2 11041573 | 12-02-1999 |
| EP 766468 | | AU A1 65840/96 | 10-04-1997 |
| | | AU B2 701639 | 04-02-1999 |
| | | CA AA 2184949 | 29-03-1997 |
| | | EP A2 766468 | 02-04-1997 |
| | | JP A2 9191394 | 22-07-1997 |



PCT

WORLD INTELLECTUAL PROPERTY ORGANIZATION
International Bureau

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 6 :
G06F 12/14

A1

(11) International Publication Number: WO 99/63443

(43) International Publication Date: 9 December 1999 (09.12.99)

(21) International Application Number: PCT/SG98/00039

(22) International Filing Date: 1 June 1998 (01.06.98)

(71) Applicant *(for all designated States except US)*: DATAMARK TECHNOLOGIES PTE LTD. [SG/SG]; Innovation Centre, Block 1, Suite 106, 16 Nanyang Drive, Singapore 637722 (SG).

(72) Inventors; and

(75) Inventors/Applicants *(for US only)*: HO, Anthony, Tung, Shuen [GB/SG]; Nanyang Technological University, School of Electrical & Electronic Engineering, Block S2, Nanyang Avenue, Singapore 639798 (SG). TAM, Siu, Chung [SG/SG]; Nanyang Technological University, School of Electrical & Electronic Engineering, Block S2, Nanyang Avenue, Singapore 639798 (SG).

(74) Agents: HAQ, Murgiana et al.; Haq & Namazie Partnership, Robinson Road, P.O. Box 765, Singapore 901515 (SG).

(81) Designated States: AU, CA, CN, ID, JP, KR, SG, US, European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE).

**Published**
*With international search report.*

(54) Title: METHODS FOR EMBEDDING IMAGE, AUDIO AND VIDEO WATERMARKS IN DIGITAL DATA

(57) Abstract

A method for embedding an entire image, audio or video watermark sequence within another image, audio or video data sequence with minimum loss of data quality is presented. The method exploits the de–correlation property of data coefficients in the orthogonal transform domain, similar to the application in data compression through transform coding. The present invention describes the usage of a Discrete Cosine Transform as the embedding domain. However, other orthogonal transforms such as Fourier, Walsh–Hadamard, Haar, Sine and Wavelet can also be used for this operation. A unique key derived adaptively from spatial locations registering the thresholds of the ac transform energies is used to unlock or de–watermark the embedded image or audio sequence. Moreover, an exponential filter has been developed to compress and expand the watermark coefficients prior to the embedding and retrieval process. The method can be used in resolving multimedia copyright protection issues arising on the Internet and in the music industry, such as the inclusion of a company's logo or an artist's recorded voice. The method can also be incorporated as a built–in feature for digital recording devices, such as still and video cameras, as well as more recent devices such as VCD and DVD players. Moreover, the method can be applied to the commercial and service sectors, where security in transmission and reception of private information in terms of speech or image is of the utmost importance.



*FOR THE PURPOSES OF INFORMATION ONLY*

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| **AL** | Albania | **ES** | Spain | **LS** | Lesotho | **SI** | Slovenia |
| **AM** | Armenia | **FI** | Finland | **LT** | Lithuania | **SK** | Slovakia |
| **AT** | Austria | **FR** | France | **LU** | Luxembourg | **SN** | Senegal |
| **AU** | Australia | **GA** | Gabon | **LV** | Latvia | **SZ** | Swaziland |
| **AZ** | Azerbaijan | **GB** | United Kingdom | **MC** | Monaco | **TD** | Chad |
| **BA** | Bosnia and Herzegovina | **GE** | Georgia | **MD** | Republic of Moldova | **TG** | Togo |
| **BB** | Barbados | **GH** | Ghana | **MG** | Madagascar | **TJ** | Tajikistan |
| **BE** | Belgium | **GN** | Guinea | **MK** | The former Yugoslav Republic of Macedonia | **TM** | Turkmenistan |
| **BF** | Burkina Faso | **GR** | Greece | | | **TR** | Turkey |
| **BG** | Bulgaria | **HU** | Hungary | **ML** | Mali | **TT** | Trinidad and Tobago |
| **BJ** | Benin | **IE** | Ireland | **MN** | Mongolia | **UA** | Ukraine |
| **BR** | Brazil | **IL** | Israel | **MR** | Mauritania | **UG** | Uganda |
| **BY** | Belarus | **IS** | Iceland | **MW** | Malawi | **US** | United States of America |
| **CA** | Canada | **IT** | Italy | **MX** | Mexico | **UZ** | Uzbekistan |
| **CF** | Central African Republic | **JP** | Japan | **NE** | Niger | **VN** | Viet Nam |
| **CG** | Congo | **KE** | Kenya | **NL** | Netherlands | **YU** | Yugoslavia |
| **CH** | Switzerland | **KG** | Kyrgyzstan | **NO** | Norway | **ZW** | Zimbabwe |
| **CI** | Côte d'Ivoire | **KP** | Democratic People's Republic of Korea | **NZ** | New Zealand | | |
| **CM** | Cameroon | | | **PL** | Poland | | |
| **CN** | China | **KR** | Republic of Korea | **PT** | Portugal | | |
| **CU** | Cuba | **KZ** | Kazakstan | **RO** | Romania | | |
| **CZ** | Czech Republic | **LC** | Saint Lucia | **RU** | Russian Federation | | |
| **DE** | Germany | **LI** | Liechtenstein | **SD** | Sudan | | |
| **DK** | Denmark | **LK** | Sri Lanka | **SE** | Sweden | | |
| **EE** | Estonia | **LR** | Liberia | **SG** | Singapore | | |

# Methods for Embedding Image, Audio and Video Watermarks in Digital Data

## FIELD OF THE INVENTION

This invention relates generally to the digital communications and multimedia fields and in particular the invention provides a method for the embedding and retrieval of digital image, audio or video watermarks in the transform domain for digital multimedia data, with applications in copyright protection and security data transmission and reception.

## BACKGROUND OF THE INVENTION

The tremendous growth in multimedia products and services through the Internet has led to the need for copyright protection, authentication and integrity of data. In the past few years, a number of digital watermarking techniques have been developed and patents granted, for the purpose of resolving the legal use or misuse of copyright information on the Internet. Unlike data encryption that transforms the original data to another form for security transmission, digital watermarking embeds an invisible or inaudible watermark directly into the original data.

Typical examples of recent work in the field of digital watermarking or data embedding are described in U.S. Patent 5636292 to Rhoads (1997) and U.S. Patent 5659726 to Sandford and Handel (1997). Rhoads discloses methods for embedding an identification code on a carrier signal, such as an electronic data signal or a physical medium. Sandford and Handel disclose a method of embedding auxiliary information into a set of host data, such as a photograph, or a television signal.

Prior art publications in the field of digital watermarking technology, including the two aforementioned granted U.S. Patents, generally envisage only the embedding of a very limited number of bits of information (in the form of binary digits '1' and '0') or a few characters (such as 'A12') into the carrier signal. More detailed ownership information requires a higher level of embedded watermark information either in the form of longer alphanumeric character strings or, if possible, trademarks/logo images, or speech of the original owner, which is embedded into and retrieved from the carrier signal. However, this has previously been considered to be very difficult to achieve, without significant corruption of the data being labelled as the amount of data to be inserted is increased. The present invention describes such a method for embedding digital audio or image watermarks directly into targeted audio or image data, substantially inaudibly or invisibly, respectively.

There are many other potential consumer, commercial and service applications that can benefit from the use of digital watermarking technology in copyright protection

and security transmission. These applications include the embedding of owner identification, such as the trademarks or logos of an owner into digital still and video cameras, or copyright protection and royalty tracking monitoring of sound recordings in the music industry with digital audio watermarks of the artists' voice embedded into the sound tracks.

Furthermore, commercial and service sectors are also interested in the secure transmission and reception of sensitive messages, data, and even images that could be camouflaged into normal data streams transmitted over an open channel.

## SUMMARY OF THE INVENTION

In this specification and claims the term "unlabelled data" is to be given the meaning of target data to which a new label is to be added by the method of the present invention, whether or not that target data is carrying a previously applied label. Similarly the term "labelled data" is to be given the meaning of target data to which the new label has been added by the method of the present invention.

According to a first aspect, the present invention provides a method for applying digital watermarking image data or digital watermarking audio data to an unlabelled digital image, audio, or video data sample, said method including the steps of :

a) inputting a set of unlabelled digital data and a set of digital watermark data;

b) formatting the unlabelled digital data into a format suitable for orthogonal transformation;

c) performing an orthogonal transformation on the formatted unlabelled data to produce a set of unlabelled data transform coefficients;

d) formatting the digital watermark data into a format suitable for orthogonal transformation;

e) performing an orthogonal transformation on the formatted watermark data to produce a set of watermark data transform coefficients;

f) for each watermark data transform coefficient, allocating an unlabelled data transform coefficient to be replaced and replacing the respective unlabelled data transform coefficients to produce a labelled set of data transform coefficients;

g) storing the locations into which watermark data transform coefficients were encoded in the set of labelled data transform coefficients to generate a unique key for future decoding of the watermark data;

h) performing an inverse orthogonal transformation on the labelled data transform coefficients to convert them into a set of labelled digital data having a form resembling the original unlabelled digital data.

Preferably, the steps of formatting the unlabelled and watermarked data include the steps of mapping the set of unlabelled data and the set of watermark data into two-dimensional matrices prior to performing the orthogonal transformations.

Preferably also the matrices of unlabelled and watermark data are divided into smaller sub-blocks prior to orthogonal transformation.

The preferred method further includes the step of ordering the orthogonal transformation coefficients in each sub-block of the watermark data into one-dimensional arrays in approximately increasing frequency order (throughout the specification and claims, the term "approximately increasing frequency order" is used in respect of one-dimensional arrays of orthogonal transform coefficients to indicate that the coefficients of the array are ordered in generally increasing frequency order, from the first to the last position in the array, with only occasional localised deviations from the generally increasing trend) by performing a zig-zag scan of each sub-block of orthogonally transformed watermark data. The reordered orthogonal transformation coefficients are then divided into segments for subsequent replacement into the set of transformation coefficients of the unlabelled data.

The preferred method further includes the step of ordering the orthogonal transformation coefficients of the unlabelled data into one-dimensional arrays in approximately increasing frequency order by performing a zig-zag scan of each sub-block of orthogonally transformed unlabelled data prior to replacement of the watermark data coefficients and performing an inverse zig-zag scan on the labelled data coefficients prior to the inverse orthogonal transformation. In the step of allocating a segment of the orthogonally-transformed watermark data that will be encoded in each sub-block of the unlabelled data, the allocation may be performed in a structured or random manner.

Alternatively, the zig-zag and inverse zig-zag scans of each data type can be replaced with a radial and inverse radial scans respectively.

It is also preferable to calculate the mean and variance of the ac energies from the orthogonal transformation coefficients for each sub-block of the unlabelled data in order to allocate the locations of the transform coefficients of the unlabelled data which will be replaced by the transform coefficients of the segment of watermark data. Preferably the transform coefficients to be replaced in the transformed unlabelled data will be those in which the ac energies fall below a predetermined threshold value.

The transform coefficients of the watermark data embedded in the labelled digital data are also preferably compressed prior to embedding, using a scaling function. Preferably the compression function has an exponential characteristic, however in other embodiments scaling functions having another characteristic similar to an exponential function may be used to similar effect.

According to a second aspect, the present invention provides a method for extracting digital watermarking image data or digital watermarking audio data from a digital image, audio, or video data sample, said method including the steps of:

a) inputting a set of labelled digital data and unique key data containing information of locations of watermark data imposed as a label on the labelled digital data;

b) mapping the set of labelled digital data into a format suitable for orthogonal transformation;

c) performing an orthogonal transformation on the formatted labelled data to produce a set of labelled data transform coefficients;

d) using the unique key to extract a segment of transform coefficients of orthogonally transformed watermark data from the locations in the set of labelled data transform coefficients specified in the key;

e) using an inverse orthogonal transformation on the transformed watermark data to retrieve the embedded watermark data.

Preferably, the formatting step of the watermark extraction method includes the step of mapping the set of labelled data into a two-dimensional matrix prior to performing the orthogonal transform.

Preferably also, prior to orthogonal transformation, the matrix of labelled data is divided into the same number of smaller sub-blocks as that used in the encoding process.

It is also preferable to order the orthogonal transformation coefficients of the labelled data in each sub-block into a one-dimensional array in approximately increasing frequency order by performing a zig-zag scan of each sub-block of orthogonally transformed labelled data prior to extraction of the watermark data coefficients and performing an inverse zig-zag scan on the extracted watermark data coefficients to build a matrix of sub-blocks of watermark data prior to the inverse orthogonal transformation. In some embodiments of the invention a radial scan is used in the encoding process of the unlabelled data to order the unlabelled data prior to replacement with watermark data in which case a radial scan and inverse radial scan

should also be used in the decoding process instead of respectively a zig-zag scan and inverse zig-zag scan.

The transform coefficients of the watermark data embedded in the labelled digital data are also preferably compressed prior to embedding and the extraction method includes the step of expanding the compressed watermark data prior to the inverse orthogonal transformation, the compression and expansion steps using scaling functions each having a characteristic which is the inverse of the other. Preferably the compression function has an exponential characteristic and the expansion function has an inverse exponential characteristic. In other embodiments scaling functions having characteristics similar to an exponential and inverse exponential function respectively may be used to similar effect.

In embodiments of the invention, the retrieved watermark data samples may either be displayed as a visual or audio output of the encoding process for immediate examination or authentication, or may be stored as a digital file for future visual or aural examination or authentication or for digital comparison with a master reference file.

Preferably, the orthogonal transform is a Discrete Cosine Transform (DCT) and the inverse transform is an inverse DCT, however, other orthogonal transforms such as Fourier, Walsh-Hadamard, Haar, Sine, and Wavelet transforms can also be used.

The unlabelled digital data samples may be obtained from a sample stream representing a digitised grayscale or colour image, for example, as provided by a digital still camera. Alternatively, the unlabelled digital data may be obtained from a sample stream representing digitised video in which case the source may be a video camera or a master tape of video program material.

In the second aspect of the invention, the labelled data prior to decoding, will in most cases be obtained from some form of recording such as a recording on a Video CD (VCD), a Laser Disc (LD) or a Digital Versatile Disc (DVD) carrying a recording of the labelled data as the digitised video in a digitised movie or still image contained within a video game or other software. The labelled data may also be obtained from a broadcast transmission.

The unlabelled and labelled digital data may also be a part of an audio signal in which case it may be a digitised sample stream representing digitised sound or music and may include two sample streams representing channel A and channel B of digitised stereo sound, each of which or either will be encoded with watermark data.

In the case of audio data, the transmission step might involve recording the labelled data on a Compact Disc (CD), Digital Audio Tape (DAT), a Laser Disc (LD), a Video CD (VCD), live digital broadcast, or live digital music or conversation down a communication channel such as a telephone line or phone through internet.

The labelled digital data may also be a part of an image or a video signal that contains a digitised audio segment as watermark data. In this case, the transmission step might involve recording the labelled data on a video CD, a digital versatile disc (DVD), a laser disk or live transmission of images or video signals down a communication channel such as a telephone line or through the internet.

Preferably, the watermark digital data will include one or more of: an owner's logo, an owner's trademark, a personal identification, an artist's recorded voice or, general terms for publisher distribution.

Embodiments of the present invention provide a digital watermarking method that embeds and retrieves either digital audio or image watermarks in the temporal (one-dimensional) and spatial (two-dimensional) domain of digital data. Compared with existing methods, which target mainly the embedding of alphanumeric character codes as watermarks, embodiments of the present invention have the distinct advantage of embedding and retrieving an entire audio or image watermark into various digital data formats, inaudibly or invisibly, respectively.

Digital watermarking methods according to the preferred embodiment of the invention are truly generic in the sense that they can be applied to many different formats of digital media. The method operates on orthogonal transform coefficients of the data source. The advantages of using orthogonal transforms in the field of digital image processing such as data compression, restoration, enhancement and pattern recognition have been well documented in the literature. The main advantage of using orthogonal transforms instead of a temporal or spatial domain is the de-correlation processes that result in fewer coefficients with significant energies of interest. Subsequently, a number of data processing techniques such as filtering and thresholding can be directly applied to the transform coefficients.

Using embodiments of the present invention, a digital image of a trademark or logo can be embedded into and retrieved from a grayscale or colour image stored in either BMP, GIF, TIFF, JPEG or MPEG format. In audio watermarking, the same method can be used to embed a signature audio sequence into typical audio formats such as WAV and AIFF or into images or video signals. This method can also be extended to embedding audio watermarks in digital image or video data, such as DVD and VCD formats, or live signals through the internet or down a telephone line.

Correlation studies performed on many experimental tests of the present invention have revealed that the labelled (embedded or watermarked) data and the original unlabelled data can result in high correlation coefficient value in the range of approximately 0.91 to 0.99 (When there are absolutely no differences between two images, the correlation value would equal to 1.). The present method exploits the de-correlation property of coefficients in the transform domain for watermark embedding. In the transform domain, most of transform coefficient energies are associated with only a few low frequency coefficients thus the watermark data can be embedded in the high frequency region.

With the tremendous growth in products and services provided through the Internet, the need for copyright protection, authentication and integrity of digital data is rapidly increasing in importance. With the present method, a company's logo or trademark can be embedded entirely into a digital image invisibly or into a sound track inaudibly. The hidden data or watermark can then be subsequently used in resolving copyright protection issues.

Consumer products, such as digital still and video cameras, can also exploit the benefits of this invention as a built-in feature of their integrated technology, for example in copyright protection and product identification. Digital watermarking can also be very useful in commercial and personal communications. For example, classified or sensitive information can be embedded within an audio, digital still/video data for secure transmission and reception.

Preferably, embodiments of the invention provide the same generic functional capability of a digital watermarking method whether the digital audio, or image watermark is embedded into any one of various data formats, such as grayscale and colour images, or audio or video data.

According to a third aspect, the present invention provides apparatus for applying digital watermarking image data or digital watermarking audio data to an unlabelled digital image, audio, or video data sample, said apparatus including:

a) input means arranged to input a set of unlabelled digital data;

b) processing means arranged to process the unlabelled digital data to encode watermark data into the unlabelled data to form a set of labelled digital data; and

c) output means arranged to output the labelled digital data to a communication or storage medium,

wherein the processing means is arranged to perform the method as herein described.

According to a fourth aspect, the present invention provides an apparatus for extracting digital watermarking image data or digital watermarking audio data from labelled digital image, audio, or video data sample said apparatus including:

a) input means arranged to input a set of labelled digital data;

b) processing means arranged to process the labelled digital data to extract watermark data encoded into the labelled digital data; and

c) output means arranged to output the extracted watermark digital data to a display or storage means,

wherein the processing means is arranged to perform the method as herein described.

According to a fifth aspect, the present invention provides a digital recording, recorded on any recording medium, the recording being encoded with watermark data in accordance with the methods described.

## BRIEF DESCRIPTION OF THE DRAWINGS

Embodiments of the invention will now be described, by way of example, with reference to the accompanying drawings in which:

Figure 1 illustrates a step of sub-blocking a matrix for orthogonal transformation used in embodiments of the invention;

Figure 2 illustrates a zig-zag scanning technique used in an embodiment of the invention, as compared to conventional line-by-line or raster scanning;

Figure 3 illustrates an image a) before and b) after a step of performing a Discrete Cosine Transform (DCT) on the sub-blocks of the image used in an embodiment of the invention;

Figure 4 illustrates an exponential curve used in a step of re-scaling the transform coefficients used in embodiments of the invention;

Figure 5 illustrates a step of embedding the watermark coefficients in a structured manner in accordance with an embodiment of the invention;

Figure 6 illustrates a step of embedding the watermark coefficients in a random manner in accordance with another embodiment of the invention;

Figure 7 illustrates a schematic block diagram of an embodiment of the present invention for embedding and retrieval of digital watermarks through orthogonal transformation;

Figure 8 illustrates a pseudocode listing of the embodiment of figure 7 providing a digital watermarking system that can apply to audio, image or video data.

Figure 9 illustrates an example of digital image watermarking of a company's logo, of size 128 x 128, into a real image, of size 512 x 512, of a woman's face, created using an embodiment of the present invention;

Figure 10 illustrates another example of digital image watermarking of a company's logo, of size 128 x 128, into a real image, of size 512 x 512, of a satellite image, created using an embodiment of the present invention;

Figure 11 illustrates a block diagram of a communications encoder/decoder for hidden data encoded on a communications channel;

Figure 12 illustrates a block diagram of a multimedia encoder/decoder for watermark data; and

Figure 13 illustrates a block diagram of a personal identification card encoder/decoder.

**Detailed description of embodiments of the invention**

Embodiments of a digital watermarking method will now be described in which the coefficients of a Discrete Cosine Transform (DCT) are employed. However, implementations of the invention are not limited solely to the use of DCT, and other orthogonal transforms such as discrete Fourier, Walsh-Hadamard, Haar, Sine and Wavelet transforms can also be used to good effect. In the preferred embodiment, both unlabelled data and watermark image data are first converted into two-dimensional matrices and then divided into sub-blocks, prior to orthogonal transformation. The present invention requires that the dimension size of the unlabelled data set must be at least twice the dimension size of the watermark data in each dimension, to fulfil a requirement that is closely related to the concept of the Shannon's sampling theorem. For example, for a 512 x 512 unlabelled image, the watermark image should be typically 256 x 256 or smaller.

Preferably each sub-block of the matrices is 8 x 8 pixels, which is typically considered to be a good size for data compression applications in terms of speed and minimum blocking edge effects, introduced by the sub-blocking process. For example, 8 x 8 and 16 x 16 are commonly used in JPEG and MPEG formats, however other sub-block dimensions may also usefully be employed. After sub-blocking, the individual sub-block data are then mapped into the transform domain through a DCT operation. The respective transform coefficients are then operated on by a number of processing steps necessary for digital watermarking. Figure 1 illustrates the 8 x 8 sub-blocking blocking process in which a matrix 12 is divided into a plurality of 8x8 sub-blocks 10 for orthogonal transformation.

Referring to Figure 2, the first processing step in the transform domain is to re-arrange the transform coefficients of the unlabelled and watermark data by performing a zig-zag scan of each sub-block. The zig-zag scanning technique has been used extensively in data compression. This technique essentially re-orders the transform coefficients from low frequency to high frequency in an approximately ascending manner. For example, for a two-dimensional sub-block of size, M x N, the dc transform coefficient or zero frequency component, is located at (1,1), and the other ac transform coefficients are at the following locations, (1,2), (1,3), ..., (1,N), ..., (2,1), (2,2), (2,3),..., (2,N), ...,(M,1), (M,2), (M,3), ..., (M,N). The zig-zag scanning technique will re-order the coefficient locations as follows: (1,1), (1,2), (2,1), (3,1), (2,2), (1,3), (1,4), ..., (M,N). In this manner, for each sub-block, the elements in the (MxN) matrix will be mapped into a one-dimensional array of size MN. Figure 2 illustrates the zig-zag scanning technique applied to the first 8x8 sub-block 10 of Figure 1.

After zig-zag scanning, the transform coefficients are subjected to statistical analysis. In this operation, the ac transform energies of the unlabelled data are first calculated from the transform coefficients and then compared with a threshold value derived from the mean and standard deviation of the ac transform energies. The use of an adaptive energy threshold allows optimum offset positions in each one-dimensional array to be determined. The offset position in each one-dimensional array corresponds closely with the minimum ac energies within that array. Beyond this position, the transform coefficients do not play a vital role even if they are neglected. This is similar to conventional transform coding where data compression is achieved by coding only those transform coefficients with sufficient energies, which generally fall into the low frequency range. Figure 3 illustrates the DCT domain of sub-blocks of an image.

It should be noted that the statistical method described in this embodiment is not the only possible method that can be used to set the location for replacement of the watermark data. Other adaptive filtering techniques include the choice of a fixed location for each watermark block, or alternatively the flexible use of statistical data such as the mean, standard deviation, and higher-order moments.

The embedding process of watermark coefficients must avoid overwriting any relevant transform coefficients of the unlabelled data with significant ac energies, as this would introduce unnecessary errors in the unlabelled data. Locating the optimum locations is therefore not only important in reducing the errors but the locations also generate a unique key that will be used later for decoding. Through the process of embedding the unlabelled data with an invisible or inaudible watermark, the combined

data set will now become labelled data. Integrity of the labelled data depends entirely on how the ac transform coefficients of the unlabelled data are overwritten or replaced by the watermark transform coefficients, during the embedding process.

The watermark data is also grouped into a two-dimensional matrix. The data is then divided into sub-blocks. Each sub-block is subjected to DCT or other orthogonal transformation in the same way as the unlabelled data has been treated. Again, zig-zag scanning is applied to arrange the transformation coefficients in an approximately increasing frequency order. The transformation coefficients for the watermark data are then blocked into segments for structured or random embedding in the transformation coefficients of the unlabelled data. Each segment of transformation coefficients to be embedded may be subjected to an optional scaling operation. This will help to minimise the overall effect of the transformation coefficients on the unlabelled data. In one preferred embodiment, the scaling function is an exponential function, although other similar mathematical functions may also be used.

Figure 4 illustrates the adaptive filtering for re-scaling of transform coefficients that follows an exponential curve. An inverse curve to the exponential curve of Figure 4 will be used in the decoding process. Other scaling techniques such as the reciprocal function, normal, log-normal, hyper-exponential, or other appropriate probability density functions can also be used.

As the dimensional size of the unlabelled data 12 is at least twice the dimensional size of the watermark data 13, the embedding or encoding process of watermark coefficients 15 can exploit the additional sub-blocks 10 available in the unlabelled data 12. The encoding process can be performed either in a structured or random manner. For example, in a structured manner, the watermark coefficients 15 can be embedded in every odd or even column or row of the unlabelled transform coefficient locations. While in a random manner, the watermark coefficients can be located in different columns or rows, depending on a specified random sequence. Figures 5 and 6 illustrate the watermark coefficients 15 embedded in a structured 20 and random 22 manner, respectively.

One important feature of the present invention is that the sizes of both unlabelled and labelled data are compatible. For example, a 512 x 512 grayscale image, embedded with a 128 x 128 watermark grayscale image corresponds to exactly the same data size of the unlabelled image, approximately 262 kBytes. A unique key for the labelled image is generated and the size of the key is much less than the watermark grayscale image of size of 16.4 kBytes of data. The size of the key for a 512 x 512 image is only approximately 4 kBytes.

The unique key and the labelled data generated will be transmitted to the decoder for extraction of the digital watermark. For added security, the unique key can be further encrypted through some random sequence. From the unique key, the spatial locations of the embedded watermark transform coefficients are extracted for each sub-block. The extracted transform coefficients are then expanded through the application of an inverse optional exponential or other appropriate compression curve. These expanded coefficients are subsequently converted back to follow a normal scanning pattern in a two-dimensional matrix before being operated on by an inverse DCT.

Figure 7 illustrates a schematic process flow diagram of the present invention for embedding and retrieval of digital watermarks through orthogonal transformation. Referring to figure 7, the unlabelled raw data 12 and the watermark raw data 13 are first divided into sub-blocks 10, 28. Both data sub-blocks are individually transformed through a DCT 30. The transform coefficients of the sub-blocks are then re-ordered to follow a zig-zag pattern 14. Spatial locations for embedding are derived from the ac transform energies 32 of the unlabelled data 12. A unique key 34 for decoding is generated from these spatial locations. Prior to embedding the watermark coefficients onto the unlabelled spatial locations, the watermark coefficients are first compressed by an exponential filter 18. The compressed watermark coefficients are embedded 36 structurally or randomly into the unlabelled sub-block DCT coefficients. The labelled coefficients are then re-ordered from a zig-zag scan pattern back to a normal scan pattern, before an inverse DCT transformation 38 is performed on the coefficients to obtain the labelled data 39.

At the decoding end, the labelled data 38 and the unique key 34 are both read 40. The same process of forward DCT transformation 130 and zig-zag scanning 114 are also performed on the labelled data, as in the case during the embedding stage. From the labelled transform coefficients, the watermark coefficients are decoded 46 from the labelled coefficients based on the spatial locations extracted 44 from the unique key. The watermark coefficients are expanded through an inverse exponential filter 48 and re-arranged to follow a normal scan pattern. This is then followed by an inverse transformation by DCT 138 to obtain the decoded watermark data.

Figure 8a and 8b illustrate pseudocode listings of a digital watermarking coder and decoder system that can be applied to image, audio and video data. Figures 9 and 10 illustrate examples of digital image watermarking in the form of a company logo of size 128 x 128 into two real images of size 512 x 512 of a women's face and a satellite image, respectively. Correlation analysis performed on these examples between the unlabelled and labelled images and original and decoded watermarks have yielded

correlation coefficients of 0.9932 and 0.9975 for the face and watermark, respectively. While for the satellite image and its logo, the correlation coefficients for unlabelled and labelled images and original and decoded watermarks are 0.9979 and 0.9994, respectively.

The proposed method of digital watermarking of an audio sequence inaudibly or image sequence invisibly into digital data has many potential applications for resolving copyright protection issues in the consumer sector or for security transmission in the commercial and service sectors. This principle applies to personal voice communication through open-channel communication systems. For example, data watermarking of a company's logo/trademark or a person's identification can be incorporated into consumer electronic products, such as digital still/video camera and more recently, VCD and DVD players, to authenticate the true ownership of intellectual property right and consumer identification. Another major consumer area for digital watermarking is in the protection of illegal copying and downloading of music CDs and tapes. For example, the voice of the artist can be inaudibly embedded into a sound track through the use of the present invention.

In the commercial sector, the copyright protection of multimedia data on the Internet needs also to be monitored closely, as there are tremendous amount of original data in the form of music, image and video, illegally downloaded and redistributed without the consent of the true owners. The present invention can be used to address this problem, as well as providing the security transmission of embedded data in some commercial banking operations. Similarly in the service sector, sensitive audio or image data can be embedded into an ordinary speech or image for secure transmission, respectively.

Referring to Figure 11, an application of the method of the present invention is illustrated, in which input digital facsimile or telephone audio data 200, is encoded with hidden digital data 201 in a communication encoder 202 embodying an encoding method according to the invention.

The encoder 202 outputs a set of labelled digital facsimile or telephone data 203 and a unique key 204 as a result of the encoding process and these are transmitted via a communications channel 208 to a communication decoder 205 embodying a decoding method according to the invention. The decoder outputs labelled (i.e. unaltered) digital facsimile or telephone data 206 and extracted hidden data 207 which may represent a hidden message, or may be used to validate the source of the telephone facsimile data.

Turning to the embodiment of Figure 12, a further application of the method of the present invention is illustrated, in which input digital audio, image or video data

210 is encoded with digital watermark data 211 in a multimedia encoder 212 embodying an encoding method according to the invention. The encoder 212 outputs a set of labelled digital audio, video or image data 213 and unique key data 214 as a result of the encoding process and is carried as a recording on any suitable digital recording media or as a transmission over a communications or broadcast channel 218. In turn, the labelled data 213 and key data 214 are fed to a multimedia decoder 215, which extracts the watermark data and outputs the watermark data 217 and the labelled data 216. The extracted label or watermark 217 may be displayed to indicate the origin or ownership of the recording or transmission to the user of the data.

In Figure 13, yet another application of the invention is illustrated in which identification information 220 such as personal identification information from an identification (ID) card is encoded with watermark data 221 in an identification (ID) card encoder 222 such that output labelled ID data 223 may be validated at a later date. The ID card encoder 222 outputs labelled ID data 223 and a unique key 224 produced by the encoding process for transmission 228 as part of a transaction such as a credit card transaction which requires secure transmission of the card holder's identity.

A card decoder 225 which receives the transmission 228 includes a watermark decoder according to the present invention which inputs the transmitted labelled ID data 228 and the unique key 224 and outputs ID data 226 and watermark data 227. The watermark data 227 may then be used to indicate validity or otherwise of the labelled ID data 226 in an authentication process associated with the transaction.

The proposed method of data watermarking can embed audio or image data, inaudibly or invisibly, respectively, into various digital multimedia data formats, such as audio, image and video. Provided the unlabelled data dimension size is at least twice the dimension size of the watermark data, an artist's recorded voice or an entire image of a company's logo or trademark, for example, can be embedded into audio and image and video data, without any serious degradation to the data quality. The proposed method exploits the de-correlation property of orthogonal transforms for embedding and retrieving digital watermarks.

Although the proposed method describes mainly the use of a discrete cosine transform as the domain for watermarking; however, orthogonal transforms such as Fourier, Walsh-Hadamard, Haar, Sine and Wavelet can also be applied. Instead of the current watermarking technology of embedding text strings into digital data, the proposed method would provide additional complementary proof as to the true ownership of the digital data, by the use of a company's logo or a recording of the

artist's voice, making a copyright infringement claim easier to substantiate than when just a text string is applied as the watermark.

The ability of the proposed method to embed and retrieve an entire audio or image watermark is a significant advantage over current prior art techniques that could only embed very simple and limited number of bits or characters into the data. Correlation performed on digital data before and after digital watermarking using the proposed method has shown the data to be very close to one, indicating that there is minimum loss in data integrity. A significant advantage of the preferred embodiment is that the labelled and unlabelled data have the same data size. A unique key generated during the embedding process that is necessary for decoding the watermark is only fractional of the watermark data size.

Digital still and video cameras can also benefit from the proposed method as a built-in feature of their integrated technology. Moreover, digital watermarking can be useful in commercial and personal communications. For example, a classified audio or image can be embedded into digital multimedia data for secure transmission.

It will be appreciated by persons skilled in the art that numerous variations and/or modifications may be made to the invention as shown in the specific embodiments without departing from the spirit or scope of the invention as broadly described. The present embodiments are, therefore, to be considered in all respects as illustrative and not restrictive.

CLAIMS:

1. A method for applying digital watermarking image data or digital watermarking audio data to an unlabelled digital image, audio, or video data sample, said method including the steps of:

a) inputting a set of unlabelled digital data and a set of digital watermark data;

b) formatting the unlabelled digital data into a format suitable for orthogonal transformation;

c) performing an orthogonal transformation on the formatted unlabelled data to produce a set of unlabelled data transform coefficients;

d) formatting the digital watermark data into a format suitable for orthogonal transformation;

e) performing an orthogonal transformation on the formatted watermark data to produce a set of watermark data transform coefficients;

f) for each watermark data transform coefficient, allocating an unlabelled data transform coefficient to be replaced and replacing the respective unlabelled data transform coefficients to produce a labelled set of data transform coefficients;

g) storing the locations into which watermark data transform coefficients were encoded in the set of labelled data transform coefficients to generate a unique key for future decoding of the watermark data;

h) performing an inverse orthogonal transformation on the labelled data transform coefficients to convert them into a set of labelled digital data having a form resembling the original unlabelled digital data.

2. The method of claim 1 wherein the step of formatting the watermark data includes the step of mapping the set of watermark data into a two-dimensional matrix.

3. The method of claim 2 wherein the step of formatting the watermark data includes the step of dividing the two-dimensional matrix of watermark data into smaller sub-blocks and the step of performing the orthogonal transformation on the watermark data involves performing the orthogonal transform on each sub-block of the watermark data, such that the watermark data transform coefficients are organised in sub-blocks.

4. The method as claimed in claim 3, including an ordering step in which each sub-block of the watermark data transform coefficients are reordered into a one-dimensional array in approximately increasing frequency order, as hereinbefore

defined, prior to replacement of the allotted unlabelled data transform coefficients with the watermark data transform coefficients.

5. The method of claim 4, in which the step of reordering the watermark data transform coefficients of each sub-block is achieved by performing a zig-zag scan of the watermark data transform coefficients in the respective sub-block.

6. The method of claim 4, in which the step of reordering the watermark data transform coefficients of each sub-block is achieved by performing a radial scan of the watermark data transform coefficients in the respective sub-block .

7. The method as claimed in claim 4, 5 or 6, wherein after the watermark data transform coefficients of each sub-block are reordered into a one-dimensional array and before the replacement of unlabelled data transform coefficients with the watermark data the watermark data transform coefficients of each one-dimensional array are rescaled.

8. The method as claimed in claim 7, wherein the rescaling is performed using a scaling function that reduces the magnitude of lower frequency coefficients of the one-dimensional array by a greater amount than higher frequency coefficients of the respective array.

9. The method of claim 8, wherein the scaling function has an exponential characteristic.

10. The method of any one of claims 4 to 9, including the step of dividing the reordered watermark data transform coefficients of each sub-block into segments for subsequent replacement into the set of transformation coefficients of the unlabelled data.

11. The method as claimed in any one of claims 1 to 10, wherein the step of formatting the unlabelled data includes the step of mapping the set of unlabelled data into a two-dimensional matrix.

12. The method of claim 11 wherein the step of formatting the unlabelled data includes the step of dividing the two-dimensional matrix of unlabelled data into smaller sub-blocks and the step of performing the orthogonal transformation on the unlabelled data involves performing the orthogonal transform on each sub-block of the unlabelled data, such that the unlabelled data transform coefficients are organised in sub-blocks.

13. The method of claim 12, including a first ordering step in which each sub-block of the unlabelled data transform coefficients are reordered into a one-dimensional array in approximately increasing frequency order, as hereinbefore

defined, prior to replacement of allocated unlabelled data transform coefficients with watermark data transform coefficients, and a second ordering step in which each of the one-dimensional arrays of the labelled data transform coefficients are reordered into sub-blocks using an inverse reordering to that of the first ordering step.

14. The method of claim 13, wherein the first ordering step is achieved by performing a zig-zag scan of each sub-block of the unlabelled data transform coefficients and the second ordering step is achieved by performing an inverse zig-zag scan of each one-dimensional array of the labelled data transform coefficients.

15. The method of claim 13, wherein first ordering step is achieved by performing a radial scan of each sub-block of the unlabelled data transform coefficients and the second ordering step is achieved by performing an inverse radial scan of each one-dimensional array of the labelled data transform coefficients.

16. The method of claim 13, 14 or 15, including the step of, for each one-dimensional array of unlabelled data, determining a location beyond which the ac energies will fall below a certain threshold value and selecting transform coefficients beyond that location for replacement by transform coefficients of the watermark data.

17. The method of claim 16, including the step of calculating the mean and variance values of the ac energies from the orthogonal transformation coefficients for each one-dimensional array of unlabelled data and calculating the threshold value as a function of the mean and variance values.

18. The method as claimed in any one of claims 12 to 17, including the step of, for each one-dimensional array of the unlabelled data, allocating a segment of the orthogonally-transformed watermark data that will be encoded in that sub-block, if any.

19. The method as claimed in any one of claims 1 to 18, wherein the orthogonal transform performed on the unlabelled data is one of: a Discrete Cosine Transform (DCT); a Fourier transform; a Walsh-Hadamard transform; a Haar transform; a sine transform; and a Wavelet transform, and the inverse transform is respectively; an inverse DCT; an inverse Fourier transform; an inverse Walsh-Hadamard transform; an inverse Haar transform; an inverse sine transform; and an inverse Wavelet transform.

20. The method as claimed in claim 19, wherein the orthogonal transform performed on the unlabelled data is a Discrete Cosine Transform (DCT) and the inverse transform is an inverse DCT.

21. The method as claimed in any one of claims 1 to 20, wherein the orthogonal transform performed on the watermark data is one of: a Discrete Cosine

Transform (DCT); a Fourier transform; a Walsh-Hadamard transform; a Haar transform; a sine transform; and a Wavelet transform.

22. The method as claimed in claim 21, wherein the orthogonal transform performed on the watermark data is a Discrete Cosine Transform (DCT).

23. The method as claimed in any one of claims 1 to 22, including the further step of allocating in a structured manner a segment of the orthogonally-transformed unlabelled data that will be replaced by each segment of orthogonally transformed watermark data.

24. The method as claimed in any one of claims 1 to 22, including the further step of allocating in a random manner a segment of the orthogonally-transformed unlabelled data that will be replaced by each segment of orthogonally transformed watermark data.

25. The method as claimed in any one of the preceding claims wherein the set of unlabelled digital data is obtained from a sample stream representing a digitised grayscale or colour image.

26. The method as claimed in claim 25, wherein the digitised grayscale or colour image is obtained from a digital still camera or a digital image scanner.

27. The method as claimed in any one of claims 1 to 24, wherein the set of unlabelled digital data is obtained from a sample stream representing digitised video.

28. The method of claim 27, wherein the unlabelled digitised video is obtained from a Data Storage Medium (DSM), or a real time digital data source.

29. The method as claimed in claims 1 to 28, wherein the labelled digitised video is subsequently transmitted over a digital communications channel.

30. The method as claimed in any one of claims 1 to 28, wherein the labelled digitised video is subsequently recorded on a digital recording medium.

31. The method as claimed in claim 30, wherein the digital recording medium is one of: a Video Compact Disc (VCD); a Laser Disc (LD); a Digital Versatile Disc (DVD); a digitised movie and a still image contained within a video game, video-on-demand or other software.

32. The method as claimed in any one of claims 1 to 24, wherein the unlabelled digital data is obtained from a sample stream representing one or more channels of digitised sound or music.

33. The method of claim 32, wherein the unlabelled digitised sound or music is obtained from one of: a master recording on digital audio tape played on a digital tape recorder; and a master recording on an analog audio tape played on an analog tape recorder and digitised via a digitising interface.

34. The method as claimed in any one of claims 32 to 33, wherein the labelled digitised sound or music is subsequently recorded on a digital recording medium.

35. The method as claimed in claim 34, wherein the digital recording medium is one of: a compact Disc (CD); a Digital Audio Tape (DAT); a Laser Disc (LD); a Video Compact Disc (VCD).

36. The method as claimed in any one of the preceding claims wherein the watermark digital data includes one or more of the following data items: an owner's logo; an owner's trademark; a personal identification; an artist's recorded voice; or general terms for publisher distribution.

37. A method for extracting digital watermarking image data or digital watermarking audio data from a digital image, audio, or video data sample, said method including the steps of:

a) inputting a set of labelled digital data and unique key data containing information of locations of watermark data imposed as a label on the labelled digital data;

b) mapping the set of labelled digital data into a format suitable for orthogonal transformation;

c) performing an orthogonal transformation on the formatted labelled data to produce a set of labelled data transform coefficients;

d) using the unique key to extract transform coefficients of orthogonally transformed watermark data from the locations in the set of labelled data transform coefficients specified in the key;

e) using an inverse orthogonal transformation on the transformed watermark data to retrieve the embedded watermark data.

38. The method of claim 37 wherein the step of formatting the labelled data includes the step of mapping the set of labelled data into a two-dimensional matrix.

39. The method of claim 38 wherein the step of formatting the labelled data includes the step of dividing the two-dimensional matrix of labelled data into smaller sub-blocks and the step of performing the orthogonal transformation on the labelled data involves performing the orthogonal transform on each sub-block of the labelled data, such that the labelled data transform coefficients are organised in sub-blocks.

40. The method as claimed in claim 39, including the step of ordering the orthogonal transformation coefficients of the labelled data in each sub-block into a one-dimensional array in approximately increasing frequency order, as hereinbefore defined, prior to extraction of the watermark data coefficients.

41. The method as claimed in claim 40, wherein the ordering step is achieved by performing a zig-zag scan of each sub-block of orthogonally transformed labelled data.

42. The method as claimed in claim 40, wherein the ordering step is achieved by performing a radial scan of each sub-block of orthogonally transformed labelled data.

43. The method of any one of claims 37 to 42, wherein after extraction of the watermark transform coefficients from the orthogonally transformed labelled data, the extracted watermark data transform coefficients are arranged into a number of one-dimensional arrays corresponding to the number of sub-blocks used in the process of encoding the watermark data into the labelled data and each one-dimensional array is then reordered into a two-dimensional sub-block prior to performing the inverse orthogonal transform on the watermark data transform coefficients in each sub-block.

44. The method of claim 43, wherein the reordering of each one-dimensional array of watermark data transform coefficients into a respective sub-block is achieved by performing an inverse zig-zag scan.

45. The method of claim 43, wherein the reordering of each one-dimensional array of watermark data transform coefficients into a respective sub-block is achieved by performing an inverse radial scan.

46. The method as claimed in any one of claims 37 to 45, wherein the transform coefficients of the watermark data embedded in the labelled digital data are compressed using a first scaling function and the method includes the step of expanding the compressed watermark data prior to the inverse orthogonal transformation using a second scaling function which is an inverse of the first scaling function.

47. The method of claim 46, wherein the inverse scaling function increases the magnitude of lower frequency coefficients of each one-dimensional array of watermark data to a greater extent than it increases the magnitude of the higher frequency coefficients of the respective one dimensional array.

48. The method of claim 46, wherein the first scaling function has an exponential characteristic and the second scaling function has an inverse exponential characteristic.

49. The method as claimed in any one of claims 37 to 48, wherein the orthogonal transform performed on the labelled data is one of: a Discrete Cosine Transform (DCT); a Fourier transform; a Walsh-Hadamard transform; a Haar transform; a sine transform; and a Wavelet transform.

50. The method as claimed in claim 49, wherein the orthogonal transform performed on the labelled data is a DCT.

51. The method as claimed in any one of claims 37 to 50, wherein the inverse orthogonal transform performed on the watermark data is one of: an inverse Discrete Cosine Transform (DCT); an inverse Fourier transform; an inverse Walsh-Hadamard transform; an inverse Haar transform; an inverse sine transform; and an inverse Wavelet transform.

52. The method as claimed in claim 51, wherein the inverse orthogonal transform performed on the watermark data is an inverse DCT.

53. The method as claimed in any one of claims 37 to 52, including the further step of displaying the watermark data samples for immediate examination or authentication.

54. The method as claimed in any one of claims 37 to 52, including the further step of storing the watermark data samples for future examination or authentication.

55 The method as claimed in any one of claims 37 to 54, wherein the labelled digital data is obtained from a sample stream representing a digitised grayscale or colour image.

56. The method as claimed in claim 55, wherein the labelled digitised grayscale or colour image is obtained from a digital still camera or a digital image scanner.

57. The method as claimed in any one of claims 37 to 54, wherein the labelled digital data is obtained from a sample stream representing digitised video.

58. The method of claim 57, wherein the labelled digitised video is obtained from one of: a Video Compact Disc (VCD) played on a VCD player; a Laser Disc (LD) played on a LD player; a Digital Versatile Disc (DVD) played on a DVD player; a digitised movie or still image contained within a video game or other software or a digital signal transmitted over a communications channel.

59. The method as claimed in any one of claims 37 to 54, wherein the labelled digital data is obtained from a sample stream representing one or more channels of digitised sound or music.

60. The method of claim 59, wherein the labelled digitised sound or music is obtained from one of: a Compact Disc (CD) played on a CD player; a Digital Audio Tape (DAT) played on a DAT player; a Laser Disc (LD) played on a LD player; from a Video Compact Disc (VCD) played on a VCD player.

61. The method as claimed in any one of claims 37 to 60, wherein the watermark digital data includes one or more of the following data items: an owner's logo; an owner's trademark; a personal identification; an artist's recorded voice; and general terms for publisher distribution.

62. An apparatus for applying digital watermarking image data or digital watermarking audio data to an unlabelled digital image, audio, or video data sample, said apparatus including:

a) input means arranged to input a set of unlabelled digital data;

b) processing means arranged to process the unlabelled digital data to encode watermark data into the unlabelled data to form a set of labelled digital data; and

c) output means arranged to output the labelled digital data to a communication or storage medium,

wherein the processing means is arranged to perform the method as claimed in any one of claims 1 to 36.

63. An apparatus for extracting digital watermarking image data or digital watermarking audio data from a labelled digital image, audio, or video data sample said apparatus including:

a) input means arranged to input a set of labelled digital data;

b) processing means arranged to process the labelled digital data to extract watermark data encoded into the labelled digital data; and

c) output means arranged to output the extracted watermark digital data to a display or storage means,

wherein the processing means is arranged to perform the method as claimed in any one of claims 37 to 61.

64. A digital recording stored on any digital recording medium, the recording comprising a set of digital image, audio, or video data labelled with a watermark comprising a set of digital watermark image data or a set of digital watermark audio data, the set of labelled digital data being created by encoding a set of unlabelled digital data with the set of digital watermark data using the method as claimed in any one of claims 1 to 36.




FIGURE 1




FIGURE 2

(a)



(b)

FIGURE 3


Rescaling factor
1
0.9
0.8
0.7
0.6
0.5
0.4
0.3
0.2
0.1
0
0
10
20
30
40
50
60
70
Data samples

FIGURE 4




**FIGURE 5**




**FIGURE 6**


Read Data
Unlabelled Data (12)
Watermark Data (13)
Sub-block Unlabelled data (10) Watermark data (28)
Forward DCT (30) & zig-zag Scan (14)
Unlabelled DCT Data
Watermark DCT Data
Normal Scan & Inverse DCT (38)
Encode Watermark Data to Unlabelled Data (36)
Re-scaling Data by Exponential Filter (18)
Read Labeled Data (40)
Determine Spatial Locations (32)
Forward DCT (130) & zig-zag Scan (114)
Read Unique Key (42)
Generate Unique Key (34)
Encoding Process
Decode Watermark DCT (46)
Extract Spatial Locations (44)
Decoding Process
Expand Data by Inverse Exponential Filter (48)
Normal Scan & Inverse DCT (138)
Decoded Watermark Data (50)

**FIGURE 7**

```
*PSEUDOCODE*

PROCEDURE WATERMARK CODER

BEGIN
        READ UNLABELLED DATA;
        CONVERT UNLABELLED DATA TO MATRIX (M,N);
        PERFORM SUB-BLOCKING of UNLABELLED DATA;
        PERFORM DCT ON UNLABELLED DATA SUB-BLOCKS;
        RE-ORDER DCT COEFFICIENTS TO FOLLOW ZIG-ZAG PATTERN;
        DETERMINE AC ENERGIES OF DCT COEFFICIENTS;
        SET THRESHOLD BASED ON AC ENERGY MEAN AND STANDARD
        DEVIATION;
        COMPARE SUB-BLOCK AC ENERGIES WITH THRESHOLD;
        IF AC ENERGIES LESS THAN THRESHOLD THEN
                STORE SPATIAL LOCATIONS;
        ELSE
                SET TO OFFSET SPATIAL LOCATIONS;
        END
        GENERATE UNIQUE KEY FROM STRUCTURED/RANDOM SPATIAL
        LOCATIONS;
        STORE UNIQUE KEY FOR DECODING;

        READ WATERMARK DATA;
        CONVERT WATERMARK DATA TO MATRIX (J,K);
        PERFORM SUB-BLOCKING of WATERMARK DATA;
        PERFORM DCT ON UNLABELLED DATA SUB-BLOCKS;
        RE-ORDER DCT COEFFICIENTS TO FOLLOW ZIG-ZAG PATTERN;
        RE-SCALE DCT COEFFICIENTS USING EXPONENTIAL FILTER;

        EMBED RE-SCALED WATERMARK DCT COEFFICIENTS INTO
        UNLABELLED DCT SUB-BLOCKS;
        CONVERT ZIG-ZAG SCAN BACK TO NORMAL SCAN;
        INVERSE DCT SUB-BLOCKS TO OBTAIN LABELED DATA;
END
```

**FIGURE 8a**

```
*PSEUDOCODE*

PROCEDURE WATERMARK DECODER

BEGIN
        READ LABELED DATA;
        CONVERT LABELED DATA TO MATRIX (M,N);
        PERFORM SUB-BLOCKING of LABELED DATA;
        PERFORM DCT ON LABELED DATA SUB-BLOCKS;
        RE-ORDER DCT COEFFICIENTS TO FOLLOW ZIG-ZAG PATTERN;

        EXTRACT SPATIAL LOCATIONS FROM UNIQUE KEY;
        DECODE WATERMARK DCT COEFFICIENTS FROM SPATIAL
        LOCATIONS;
        SCALE WATERMARK DCT COEFFICIENTS USING INVERSE
        EXPONENTIAL FILTER;
        CONVERT ZIG-ZAG SCAN BACK TO NORMAL SCAN;
        INVERSE DCT SUB-BLOCKS TO OBTAIN WATERMARK DATA;
END
```

**FIGURE 8b**

(a)


(b)

(a)


(b)

FIGURE 9



(a)


(b)



(a)


(b)

**FIGURE 10**




**FIGURE 11**




**FIGURE 12**




**FIGURE 13**

# INTERNATIONAL SEARCH REPORT

International application No.
PCT/SG 98/00039

A. CLASSIFICATION OF SUBJECT MATTER

IPC[6]: G 06 F 12/14

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC[6]: G 06 F 12/14

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

EPODOC, WPI, PAJ

C. DOCUMENTS CONSIDERED TO BE RELEVANT

| Category* | Citation of document, with indication, where appropriate, of the relevant passages | Relevant to claim No. |
|---|---|---|
| A | EP 0 840 513 A (NIPPON ELECTRIC) 06 Msy 1998 (06.05.98), abstract. | 1 |
| T | EP 0 855 681 A (NIPPON TELEGRAPH & TELEPHONE) 29 July 1998 (29.07.98), abstract. | |
| A | EP 0 766 468 A (NIPPON ELECTRIC) 02 April 1997 (02.04.97), abstract. | 1 |

---

☐ Further documents are listed in the continuation of Box C. ☒ See patent family annex.

* Special categories of cited documents:
„A" document defining the general state of the art which is not considered to be of particular relevance
„E" earlier application or patent but published on or after the international filing date
„L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
„O" document referring to an oral disclosure, use, exhibition or other means
„P" document published prior to the international filing date but later than the priority date claimed

„T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
„X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
„Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
„&" document member of the same patent family

| Date of the actual completion of the international search | Date of mailing of the international search report |
|---|---|
| 11 May 1999 (11.05.99) | 21 May 1999 (21.05.99) |

| Name and mailing adress of the ISA/AT | Authorized officer |
|---|---|
| Austrian Patent Office<br>Kohlmarkt 8-10; A-1014 Vienna<br>Facsimile No. 1/53424/535 | Fastenbauer<br><br>Telephone No. 1/53424/447 |

Form PCT/ISA/210 (second sheet) (July 1998)

# INTERNATIONAL SEARCH REPORT

Information on patent family members

International application No.
PCT/SG 98/00039

| In Recherchenbericht angeführtes Patentdokument Patent document cited in search report Document de brevet cité dans le rapport de recherche | Datum der Veröffentlichung Publication date Date de publication | Mitglied(er) der Patentfamilie Patent family member(s) Membre(s) de la famille de brevets | Datum der Veröffentlichung Publication date Date de publication |
|---|---|---|---|
| EP 840513 | | AU A1 44340/97 | 07-05-1998 |
| | | CA AA 2219205 | 05-05-1998 |
| | | EP A2 840513 | 06-05-1998 |
| | | JP A2 10145757 | 29-05-1998 |
| EP 855681 | | EP A2 855681 | 29-07-1998 |
| | | JP A2 10210427 | 07-08-1998 |
| | | JP A2 10257300 | 25-09-1998 |
| | | JP A2 10304323 | 13-11-1998 |
| | | JP A2 11018064 | 22-01-1999 |
| | | JP A2 11041573 | 12-02-1999 |
| EP 766468 | | AU A1 65840/96 | 10-04-1997 |
| | | AU B2 701639 | 04-02-1999 |
| | | CA AA 2184949 | 29-03-1997 |
| | | EP A2 766468 | 02-04-1997 |
| | | JP A2 9191394 | 22-07-1997 |